



SAB SWADAYA
PERUMAHAN THE SPRING VILLE
DS.SUKARAYA, KEC.KARANG BAHAGIA,KAB.BEKASI



RENCANA ANGGARAN BIAYA

1. PERUBAHAN JARINGAN PIPA UTAMA UKURAN 2" KE 3" DARI TOWER FASOS 2
2. PEMBUATAN VALVE KONTROL (BLOK W,X,Y, SA S/D SE)
3. INSTALASI TAMBAHAN PIPA JARINGAN (RING INSTALASI)

DATE	10 Aug 2026	S/D	12 Aug 2026				
NO	RINCIAN BIAYA	JUMLAH	UNIT	TOTAL (Rp)		TOTAL (Rp)	
				EST HARGA/UNIT	BUDGET	AKTUAL	BALANCE
1	PERUBAHAN JARINGAN PIPA UTAMA UKURAN 2" KE 3"				Rp 12.004.795	Rp -	Rp 12.004.795
	PIPA AW 3" (ALDERON)	57	BTG	Rp 139.160	Rp 7.932.120		
	PIPA AW 2" (ALDERON)	5	BTG	Rp 67.275	Rp 336.375		
	VALVE 3"	5	PCS	Rp 300.000	Rp 1.500.000		
	VALVE 2"	2	PCS	Rp 55.500	Rp 111.000		
	KNEE T 3"	12	PCS	Rp 50.000	Rp 600.000		
	KNEE L 3"	3	PCS	Rp 40.000	Rp 120.000		
	VLOK SOCK 3 X 2	2	PCS	Rp 21.500	Rp 43.000		
	VLOK SOCK 3 X 1	11	PCS	Rp 20.000	Rp 220.000		
	VLOK SOCK 2 X 1	2	PCS	Rp 9.900	Rp 19.800		
	CLAM BESI 3"	150	PCS	Rp 1.500	Rp 225.000		
	CLAM BESI 2"	150	PCS	Rp 1.100	Rp 165.000		
	CLAM BESI 1"	400	PCS	Rp 800	Rp 320.000		
	SEALTAPE	5	PCS	Rp 5.500	Rp 27.500		
	LEM PIPA	5	KALENG	Rp 65.000	Rp 325.000		
	SEMEN	1	SAK	Rp 60.000	Rp 60.000		
2	PEMBUATAN VALVE KONTROL (BLOK W,X,Y, SA S/D SE)				Rp 634.000	Rp -	Rp 634.000
	KNEE T 1"	20	PCS	Rp 6.300	Rp 126.000		
	VALVE 1"	20	PCS	Rp 25.400	Rp 508.000		
3	INSTALASI TAMBAHAN PIPA JARINGAN (RING INSTALASI)				Rp 508.000	Rp -	Rp 508.000
	PIPA AW 1" (ALDERON)	15	PCS	Rp 31.000	Rp 465.000		
	KNEE L 1"	10	PCS	Rp 4.300	Rp 43.000		
4	OPERASIONAL				Rp 3.950.000	Rp -	Rp 3.950.000
	JASA INSTALASI (3 ORANG X EST 3 HARI)	1	TIM		Rp 1.350.000		
	JASA BOBOK JALAN (2 TITIK)	1	TIM		Rp 600.000		
	DANA TAKTIS				Rp 2.000.000		
	TOTAL				Rp 17.096.795	Rp -	Rp 17.096.795

TOTAL (Rp)	BUDGET	AKTUAL	BALANCE
	Rp 17.096.795	Rp -	Rp 17.096.795

NO DOC : 016/SABSWADAYA/TSV/DOC/26
BEKASI, 2 AGUSTUS 2026